



The **PROJECTOR LIFT SI-100** is a versatile product that enables the installation of projectors in environments where particular aesthetical solutions are needed.


The product has been developed to be installed inside false ceilings in order to hide projector, lift and cables, thus granting the best aesthetic and practical solution.

SI-100 is supplied with an extremely silent motor that allows a descent from a minimum of 16 cm. to a maximum extent of 97 cm.


An interesting element of this lift is a cable gathering system with a raceway where to put the cables of the projector, so they will be hidden and tidy gathered together when the projector lift is moving. The lift is supplied with **safety screws**.

* Ceiling cover plate is NOT included


Frontal view closed




Side view closed



Side view open



Maximum size projector anchoring points







Optionals:

- Čeiling tile holder (details p. 64)
- Kit RF remote control with external receiver (details p. 62)
- Interface switch 12 volt (details p. 63)
- Low voltage contact interface (details p. 62)

	TECHNICAL SPECIFICATIONS
	POWER SUPPLY
	MAXIMUM CONSUMPTION
	TORQUE
	MOTOR SPEED
	DIMENSIONS LIFT CLOSED
	DIMENSIONS LIFT OPENED
	MOUNTING PLATE TOTAL DIMENSIONS
	MOUNTING PLATE UPPER INTERNAL DIMENSIONS
	MAXIMUM SIZE FIXING POINTS OF PROJECTOR
	MAXIMUM PROJECTOR DIMENSIONS
	MAXIMUM CAPACITY
	NET WEIGHT OF THE PROJECTOR LIFT
	CABLE GATHERING SYSTEM (internal dimensions)

220-230V	- 50HZ

156 W

10 Nm

17 rpm

575x155x554 (WxHxD in mm)

575x970x554 (WxHxD in mm)

420x450 (WxD in mm)

350x450 (WxD in mm)

320x350 (WxD in mm)

560x550 (WxD in mm)

15 Kg 12 Kg

20x18 (WxH in mm)

Warranty: 5 years on the motor - 24 months on the other components