

## **PROJECTOR LIFT** SI-H L 200



Moreover it is supplied with extendable side brackets in order to allow an easy fixing of the panel of your false ceiling by adjustable threaded bars. The panel can be mounted under the projector, even if the projector is larger as the lift itself.


The lift SI-H L 200 is equipped with safety screws that prevent the lift to extent further to the preset end stop.

\* Ceiling cover plate is NOT included




## Frontal view closed 655 575 275 MAX 420 MAX 633


## Side view closed



Side view open



Maximum size fixing points projector





## Optionals:

- Ceiling tile holder (details p. 64)
- Kit RF remote control with external receiver (details p. 62)
- Interface switch 12 volt (details p. 63)
- Low voltage contact interface (details p. 62)

TECHNIC	AL SPECIF	FICATIONS

**POWER SUPPLY** MAXIMUM CONSUMPTION **TORQUE MOTOR SPEED** MINIMUM DIMENSIONS LIFT CLOSED **DIMENSIONS LIFT OPENED** MAXIMUM SIZE FIXING POINTS PROJECTOR MAXIMUM OVERALL SIZE OF PROJECTOR MAXIMUM LOAD NET WEIGHT OF THE PROJECTOR LIFT CABLE GATHERING SYSTEM

220-230V - 50HZ 184 W

20 Nm

575x255x554 (WxHxD in mm)

575x1979x554 (WxHxD in mm)

398x372 (WxD in mm) 570x600 (WxD in mm)

30 Kg

15 Kg

20x18 (WxH in mm)

Warranty: 5 years on the motor - 24 months on the other components